BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18400/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22-01-2016

Maintainance of Elumandamma badavane BBMP Building and Gym Equipments in Ward No. 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K Sankar Reddy		
				In Figures		In Words
1	307.5	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	90.0	27675.00	Rupees Ninety Only
2	373.4	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications with Primer etc complete as per specifications and directions of engineer in charge of the work	Cum	80.0	29872.00	Rupees Eighty Only
3	21.24	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	80.0	1699.20	Rupees Eighty Only
4	50	Groove Cutting : Supplying ... dia 2mm/2.5mm thick heavy gauage PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary 32 mm dia 2.5mm thick etc complete as per specifications and directions of engineer in charge of the work	Mtrs	60.0	3000.00	Rupees Sixty Only
5	2	Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work 10"X7"X3" (300X228X76mm) etc complete as per specifications and directions of engineer in charge of the work	Each	60.0	120.00	Rupees Sixty Only
6	2	8"X6"X3" (300X228X76mm)	Cum	50.0	100.00	Rupees Fifty Only
7	5	Supplying and fixing PVC/metal conduit accessories special type 32 mm Junction Box etc complete as per specifications and directions of engineer in charge of the work	Each	20.0	100.00	Rupees Twenty Only
8	2	Deep 32 mm Junction Box	Each	30.0	60.00	Rupees Thirty Only
9	5	Point Wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using Copper PVC insulated multi strand 2x1.5 Sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet gang box the other end of the wires shall be terminated with sufficient loose length in a wood PVC round block complete for each outlet Point Wiring using Class A Materials a) Short point upto 3Mtr from tapping point to out let via switch etc complete as per specifications and directions of engineer in charge of the work	Each	170.0	850.00	Rupees One Hundred Seventy Only
10	2	b) Medium point above 3mtr upto 6mtr from tapping point to out let via switch	Each	260.0	520.00	Rupees Two Hundred Sixty Only
11	3	C) Long point above 6mtrs upto 10mtrs from tapping point to outlet via switch	Each	360.0	1080.00	Rupees Three Hundred Sixty Only

K. Sankar Reddy

Executive Engineer 26/2/16
Vidyaranyapura Sub Division
Yelahanka Zone, B.B.M.P.
Bangalore-560092

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K Sankar Reddy		
				In Figures		In Words
12	30	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate 6Amps one way etc complete as per specifications and directions of engineer in charge of the work	Each	90.0	2700.00	Rupees Ninety Only
13	15	6Amps 3way Socket.	Each	160.0	2400.00	Rupees One Hundred Sixty Only
14	6	Stepped Fan Regulator	Each	520.0	3120.00	Rupees Five Hundred Twenty Only
15	5	Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluouresecent tube Group 'A' etc complete as per specifications and directions of engineer in charge of the work	Each	380.0	1900.00	Rupees Three Hundred Eighty Only
16	2	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system KPWD SR 2007-08 (P-23, I-23) Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard 56" Sweep (1400 mm) etc complete as per specifications and directions of engineer in charge of the work	Each	1950.0	3900.00	Rupees One Thousand Nine Hundred Fifty Only
17	2	Supplying and fixing superior quality modula switch mounting polyorbonate plate with ncecessary supporting back plate with required nos. of machines screwes, bolts nuts etc., complete on the existing metal/PVC box 1 to 3 Modular etc complete as per specifications and directions of engineer in charge of the work	Each	82.0	164.00	Rupees Eighty Two Only
18	3	8 Modular	Each	170.0	510.00	Rupees One Hundred Seventy Only
19	4	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate 6Amps one way etc complete as per specifications and directions of engineer in charge of the work	Each	90.0	360.00	Rupees Ninety Only
20	3	6Amps 3way Socket.	Each	160.0	480.00	Rupees One Hundred Sixty Only
21	2	Supplying and fixing 32Amps security and energy savings DP switch with key tag suitable to operate on 230 Volts 50Hz AC supply & completely wired on existing box Group A etc complete as per specifications and directions of engineer in charge of the work	Each	600.0	1200.00	Rupees Six Hundred Only
22	1	Supplying an fixing one of 230 volts PBBC bakelite staight or slant batten holder and wiring with in 60w/230 Volts lamps etc complete as per specifications and directions of engineer in charge of the work	No	60.0	60.00	Rupees Sixty Only
23	1	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required 5-32 Amps SP etc complete as per specifications and directions of engineer in charge of the work	Each	560.0	560.00	Rupees Five Hundred Sixty Only
24	1	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20"x20"x2.5" etc etc complete as per specifications and directions of engineer in charge of the work	Each	280.0	280.00	Rupees Two Hundred Eighty Only
25	2	Supplying and fixing of porcelain fuse channel with cut out on existing wooden /panel using necessary nuts, bolts and washers 32 Amps etc complete as per specifications and directions of engineer in charge of the work	Each	100.0	200.00	Rupees One Hundred Only

26/2/16

Executive Engineer
Jayanagara Division
Yelahanka Zone, B.B.M.P.
Bangalore-560092

K. Sankar Reddy

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K Sankar Reddy		
				In Figures		In Words
26	10	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class etc complete as per specifications and directions of engineer in charge of the work	Mtr	150.0	1500.00	Rupees One Hundred Fifty Only
27	10	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, P No. 69 / I No. Ia In existing trencg/duct 6Sqmm to 16 Sqmm) etc complete as per specifications and directions of engineer in charge of the work	Mtr	8.0	80.00	Rupees Eight Only
28	8	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB etc complete as per specifications and directions of engineer in charge of the work	Mtr	60.0	480.00	Rupees Sixty Only
29	4	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm dia GI pipe etc complete as per specifications and directions of engineer in charge of the work	Mtr	240.0	960.00	Rupees Two Hundred Forty Only
30	1	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers 16Sqmm etc., etc complete as per specifications and directions of engineer in charge of the work	No.	260.0	260.00	Rupees Two Hundred Sixty Only
31	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, etc complete as per specifications and directions of engineer in charge of the work	No	1950.0	1950.00	Rupees One Thousand Nine Hundred Fifty Only
32	1	Supplying and fixing of GS 478 – Adjustable Bench with Main Frame and Strength training Oval steel tube, thickness (12 gauge), Solid Steel, Stack bushing – PVC cushion guided rods, Nylon with bearing Pulleys, High Strength cable has high load carring capacity, smooth, even functioning of the workouts achieved, high life, M8, M10, M12 Bolts, Shining Silver, Powder coated painting, Orange fabric, High density virgin foam and Composite ply board with adjustable seat etc., complete as per Engineer in Charge of the work.	Nos	28692.0	28692.00	Rupees Twenty Eight Thousand Six Hundred Ninety Two Only
33	1	Supplying and fixing of GS-897 Flat Bench with 4x2 assembly area, 2/2 12 gauge PVC Pipe, Seat & High cashion red color H2x1Wx4L, 8 kg weight etc., complete as per Engineer in Charge of the work.	Nos	12516.0	12516.00	Rupees Twelve Thousand Five Hundred Sixteen Only
34	1	Supplying and fixing of GS-899 Calf Bench of 2Hx2Wx5L assembly area, shining silver powder coated, high quality red color seat, of size 2/2.12 Gauge PVC pipe, 4 kg weight, bearing high quality seated bearing etc., complete as per Engineer in Charge of the work.	Nos	36556.0	36556.00	Rupees Thirty Six Thousand Five Hundred Fifty Six Only
35	1	Supplying and fixing of GS-759 Shoulder Bench of 2Lx2Wx4H Assembly area with 2/2 12 gauge PVC pipe, High Quality Red Shing Seat, 6 Kg Unit weight etc., complete as per Engineer in Charge of the work.	Nos	7674.0	7674.00	Rupees Seven Thousand Six Hundred Seventy Four Only
36	1	Supplying and fixing of SP-102 T-Bar Row machine of 7Lx2Hx3W with 2/2 12 gauge PVC Pipe, 120 kg capacity, 20 kg weight, high quality shield bearing etc., complete as per Engineer in Charge of the work.	Nos	28692.0	28692.00	Rupees Twenty Eight Thousand Six Hundred Ninety Two Only

K. Sankar Reddy

Executive Engineer
Byatarayanapura Division

26/2/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K Sankar Reddy		
				In Figures		In Words
37		Supplying and fixing of SP-102 Small Bench of 2Hx2Wx2L high quality red shining seat, 2/2 12 gauge PVC Pipe, 4 kgs weight etc., complete as per Engineer in Charge of the work.	Nos	5903.0	5903.00	Rupees Five Thousand Nine Hundred Three Only
38	300	Supplying and fixing of S305-Chrome dumbbles, Hand Grip Rubber bolt 'L' n Bol, high quality Ms Metal used, Nichal chrome used for shining, high grade knurling for seare comfortable gripping surface encased is high quality virgin metal dumbles are stable for fitness junkides 'b' coze they provide unmatched vorsebility etc., complete as per Engineer in Charge of the work.	Kgs	260.0	78000.00	Rupees Two Hundred Sixty Only
39	250	Supplying and fixing of S125 Rubber Weight Plate of beauty chrome handles resist chipping, flaking, peeling and corrosion, medium grade knurling for a secure, comfortable gripping surface, rubber encased coating is high quality virgin rubber, plates are one of the most versatile and effective training tools and can be utilized to work your shoulders, triceps, biceps, legs and even your back etc., complete as per Engineer in Charge of the work.	Kgs	260.0	65000.00	Rupees Two Hundred Sixty Only
40	2	Supplying and fixing of SP 104 Plate Stand of 4Hx3Wx2L assembly area with shining Silver powder coated, 7 rod holder of 20 kg weight etc., complete as per Engineer in Charge of the work.	Nos	13000.0	26000.00	Rupees Thirteen Thousand Only
41	2	Supplying and fixing of SP 105 barbell stand of 1.5Lx1.5Wx1H with shining silver powder coated, 10 rod holders of 13 kg weight and 12mm thickness etc., complete as per Engineer in Charge of the work.	Nos	9400.0	18800.00	Rupees Nine Thousand Four Hundred Only
42	2	Supplying and fixing of ACS03 Dumb bell Stand of 3Hx2Wx5L Assembly area with shining silver powder coated of 25 kg and 2/2 12 Gase 7& L Ange 1.5/6 PVC pipe and M01 belt etc., complete as per Engineer in Charge of the work.	Nos	18000.0	36000.00	Rupees Eighteen Thousand Only
43	10	Supplying and fixing of Yoga Mat of 2x5 size 10mm, medium grade for a secure comfortable encased high quality virgin rubber mat etc., complete as per Engineer in Charge of the work..	Nos	708.0	7080.00	Rupees Seven Hundred Eight Only
44	5	Supplying and fixing of Barbell Rods of 8kgs 4 ft and 5ft length, Nichal chrome used for shining medium grade knurling for a secure, comfortable gripping surface, ms steel 28mm solid rod etc., complete as per Engineer in Charge of the work.	Nos	826.0	4130.00	Rupees Eight Hundred Twenty Six Only
45	10	Supplying and fixing of PUSH UP DIP STAND of 1 kg 1ft length, 12 gauge PVC pipe, high quality MS metal used etc., complete as per Engineer in Charge of the work.	Nos	2361.0	23610.00	Rupees Two Thousand Three Hundred Sixty One Only
46	5	Supplying and fixing of ANKEL WEIGHTS with 2 kgs wiehgt and 1ft length of comfortable gripping surface nylon encased coating etc., complete as per Engineer in Charge of the work.	Kgs	944.0	4720.00	Rupees Nine Hundred Forty Four Only
47	7	Supplying and fixing of Triceps handle high quality Ms Metal used Nichal chrome used for shining, high grade knurling for seare comfortable gripping surface encased is high quality virgin metal dumbles are stable for fitness junkides b coze and they provide unmatched vorsebility with 2 kgs size 2 ft length unit weight etc., complete as per Engineer in Charge of the work.	Nos	2553.5	17874.50	Rupees Two Thousand Five Hundred Fifty Three and Fifty Paise Only

489387.70

K. Sankar Reddy
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/2/16